



Eastern & North-East Frontier Railway Co-operative Bank Ltd.

34 A & B, Sashi Bhusan Dey Street, Kolkata – 700 012 | WeCare@enfrcb.in | www.enfrcb.in


Ref.No. CB/017.02.26/Tender.MB/Locker/02.2026/2025-2026

February 9, 2026

TENDER NOTICE

The Bank Authority invites sealed tenders from the reputed vendors for renovation works of Main Branch in order to start the locker facility of the Bank. The scope of work is mentioned below. Vendors are requested to submit their tenders addressing Chief Executive Officer of the Bank within 26/02/2026, 2.30 P.M.

Sl No	Description of item	Qty.	Unit.
	<u>CIVIL INTERIOR/REPAIRING WORK</u>		
1	A) Locker room		
	(i) Patch crack of plaster the wall where necessary dismantled	40	sq.m.
	(ii) Cleaning of rubbish from working site	L.S.	
	(iii) 125th Brick Wall(1:6)	48	sq.m.
	(iv) Plaster the ame wall with water proofing compound	48	sq.m.
	(v) Termite treatment the same wall	150	sq.m.
	(vi) New Door of 37" width X 7'-6" height all complete - 1 PC	30	sft
	(vii)Existing damage floor dismantled	15	sq.m.
	(viii) New vitrified floor tiles used construct	220	sft
	(ix) 75 mm the aluminium partition with glass work	240	sft
	(x) Paint with putty finish of new wall	600	sft
2	B) Store Room		
	(i) Patch Crack of plaster the wall where necessary dismantled	62	sq.m.
	(ii) Cleaning of rubbish from working site	L.S.	
	(iii) 125th Brick Wall (1:6)	62	sq.m.
	(iv) Plaster the same wall with water proofing compound	62	sq.m.
	(v) Termite treatment the same wall	160	sq.m.
	(vi) New Door of 37" width X 7'-6" height all complete - 1 pc	30	sft
	(vii) Existing damage floor dismantled	15	sq.m.
	(viii) New vitrified floor tiles used construct	160	sft
	(ix) Granite slab work	40	sft
	(x) Paint with putty finish of new wall	500	sft
3	C) New Manager Room		
	(i) New 75th aluminium partition/ mica finish wall with glass	350	sft
	(ii) Door of 36" width X 7'-6" height all complete - 2 PC	90	sft
	(iii) Existing damage floor/column 5'-0" ht dismantled	100	sq.m.
	(iv) New vitrified floor tiles/column 5'-0" used construct	250	sft
	(v) Paint with putty finish of new wall if necessary	350	sft





Eastern & North-East Frontier Railway Co-operative Bank Ltd.

34 A & B, Sashi Bhusan Dey Street, Kolkata – 700 012 | WeCare@enfrcb.in | www.enfrcb.in

4	D) Passage/ Corridor of 13.5 m long		
	(i) Patch Crack of plaster the wall where necessary dismantled	40	sq.m.
	(ii) Cleaning of rubbish from working site	L.S.	
	(iii) 3'-0" ht wall plaster remove	39	sq.m.
	(iv) New tiles on 3'-0" ht wall + 4 nos column	400	sft
	(v) Paint with putty passage ceiling & wall	200	sft
5	E) Gate Ramp Work for Disable person - 1 No		
	(i) Dismantled work	10	sq.m.
	(ii) RCC Ramp work with 1:2:4 cement concrete	3	cu.m.
	(iii) Granite/tiles work on this area	50	sft
	(iv) Collapsible gate resetting with new dimentions	L.S.	
6	E) Gate for General Person - 1 No		
	(i) Dismantled work	10	sq.m.
	(ii) New step brick work 1:6	3	cu.m.
	(iii) Granite/tiles work on this area	50	sft
	(iv) Collapsible gate resetting with new dimentions	L.S.	
7	F) NEW CUBICAL TABLE MAKING/FURNITURE WORK	300	sft
8	G) REPAIRING & CHANGE OF EXISTING RACK WITH NEW ONE	200	sft
9	H) TOTAL EXTRA WALL & CEILING PAINTING	2000	sft

Chief Executive Officer
Chief Executive Officer



**Eastern & North-East Frontier
Railway Co-operative Bank Ltd.**